

SI No	Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
24	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for suspended floors, landings, balconies and likes, thickness upto 200 mm including cost of all materials, labour complete as per specifications for heights more than 3.50m from ground level. - 0 to 5 mtrs. complete as per specifications and directions of the Engineer in charge.								
		Sqm					0.00	436.32	0.00
	Approved Amount			436.32					
25	Providing and laying in position reinforced cement concrete of design mix M25 with OPC cement @ 340kgs, with 20mm and down size graded granite metal coarse aggregates @0.70cum and fine aggregates @ 0.47cum, with superplasticiser @3lts confirming to IS9103-1999 Reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in ground floor level for roof slabs, staircase, lintels and beams retaining walls, return walls, walls (any thickness) including attached pilasters, columns, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc., including cost of all materials, labour, HOM of machinery, curing, complete but excluding cost of reinforcement as per specifications. complete as per specifications and directions of the Engineer in charge.								
		Cum							
	Deo Marvel Park								
	Ramp Concrete								
			1	7.10	2.50	0.20	3.55		
	Toilet								
	Vivekananda Park								
	Footing Raft		8	1.50	1.50	0.30	5.40		
	Column upto Plinth		8	0.20	0.40	0.90	0.58		
							9.53		
						Upto 125%	3.69	6593.89	24,314.95
						Above 125%	5.84	6593.89	38,498.40
	Approved Amount			6593.89					
26	Providing TMT steel reinforcement Fe500 for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. complete as per specifications and directions of the Engineer in charge.								
		Tn							
	For RCC Drain 60kg/cum		1	12.00	60.00		720.00		
	For Toilet 90kg/Cum		1	8.05	90.00		724.50		
							1444.50		
							1.44		
						Upto 125%	0.68	77409.71	52,251.56
						Above 125%	0.77	77409.71	59,566.77
	Approved Amount			77409.71					

Sl No	Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
27	Providing and constructing burnt brick masonry with approved quality of non-modular bricks of standard size of class designation 5.0 Newton per sqmm (table moulded) with cement mortar 1:6 for basement and superstructure including cost of materials, labour charges, scaffolding, curing complete as per specifications. complete as per specifications and								
		Cum							
	Vivekananda Park								
	For Gazebo		1	42.00		0.20	8.40		
							8.40	7318.18	61,472.69
	Approved Amount			7318.18					
28	Providing rough cement plastering 15mm thick in single coat with cement mortar 1:6, to brick masonry for base of dadoing works with sand of approved quality, providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications. complete as per specifications and directions of the Engineer in charge.								
		Sqm							
	Toilet Area Nishargha Park								
	Longer Wall		4	3.30		2.00	26.40		
	Shorter Wall		4	1.65		2.00	13.20		
	Deduction								
			-2	0.75		1.85	-2.78		
							36.83	209.43	7,712.39
	Approved Amount			209.43					
29	Providing 12mm thick cement plaster in single coat with cement mortar 1:4, to ceiling including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications. complete as per specifications and directions of the Engineer in charge.								
		Sqm							
	Toilet Area Nishargha Park								
	Slab		1	4.20		3.75	15.75		
	Toilet								
	Ceiling Plastering								
	Vivekananda Park								
	Roof Slab		1	6.40	6.10		39.04		
							54.79		
						Upto 125%	19.76	245.43	4,850.31
						Above 125%	35.03	245.43	8,596.80
	Approved Amount			245.43					
30	Providing 12mm thick cement plaster in single coat with cement mortar 1:4, to brick masonry including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications. complete as per specifications and directions of the Engineer in charge.								
		Sqm							
	Toilet Area Nishargha Park								
	Longer Wall		3	3.30		0.60	5.94		
	Shorter Wall		4	1.65		0.60	3.96		
	Deduction								

9.90

Sl No	Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
			-2	0.90		0.45	-0.81		
							9.09	222.52	2,022.74
	Approved Amount			222.52					
31	Providing 18mm thick cement plaster in single coat with cement mortar 1:6, to brick masonry including rounding off corners wherever required smooth rendering : Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications, complete as per specifications and directions of the Engineer in charge.								
		Cum							
	Toilet Area Nishargha Park								
	External Wall								
			2	3.30		2.70	17.82		
			1	3.85		2.70	10.40		
			1	3.85		0.60	2.31		
	Parafit Wall								
	Longer Wall								
			2	4.20		0.30	2.52		
	Shorter Wall								
			2	4.85		0.30	2.91		
	Deduction								
			-2	0.90		0.45	-0.81		
							35.15	267.25	9,392.36
	Approved Amount			267.25					
32	Providing and finishing external walls in two coats with waterproof cement paint of approved brand and shade to give an even shade after thoroughly brooming the surface to remove all dirt and loose powdered material, free from mortar drops and other foreign matter cost of materials, labour, complete as per specifications. - with primer. complete as per specifications and directions of the Engineer in charge.								
		Sqm							
	Vivekananda Park								
	For Gazeboo								
	For Ring Pipe								
			8	2.10		0.55	9.24		
	For Truss angle								
			3	83.00		0.46	114.54		
	For Children Play area								
	Circumference=67.00 M								
			1	67.00		0.75	50.25		
	At Building								
			1	8.00		2.25	18.00		
			1	1.40		3.45	4.83		
			1	4.10		3.45	14.15		
	At Stadium Out Side								
			1	61.00		2.50	152.50		
	At Stadium Inside								
			1	60.00		1.20	72.00		
	Nisarga Park								
	Stage Surrounding								
			1	66.00		6.00	396.00		
	Toilet Area Nishargha Park								
	External Wall								
			2	3.30		2.70	17.82		
			1	3.85		2.70	10.40		

859.72

SI No	Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
			1	3.85		0.60	2.31		
	Parafit Wall								
	Longer Wall		2	4.20		0.30	2.52		
	Shorter Wall		2	4.85		0.30	2.91		
	Deduction								
			-2	0.90		0.45	-0.81		
	Deo Marvel Park								
	Compound Wall								
	North Side		1	52.00		1.50	78.00		
	Toilet								
	Vivekananda Park								
	Wall								
			2	5.50		2.78	30.58		
			2	5.50		2.90	31.90		
	Parapet Wall		4	5.50		0.90	19.80		
			4	5.50		0.90	19.80		
	Deduction								
	Door D		-2	0.90		2.10	-3.78		
	Ventilator V		-2	3.15		0.50	-3.15		
	Ventilator V1		-2	0.60		0.50	-0.60		
	Window		-2	1.20		1.00	-2.40		
							1036.80		
						Upto 125%	45.94	111.26	5,111.08
						Above 125%	990.86	111.26	110244.95
	Approved Amount			111.26					
33	Two coats with plastic emulsion paint of approved brand on wall surface to give an even approved shade after thoroughly brushing the surface, free from mortar drops and other foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour, complete as per specifications. complete as per specifications and directions of the Engineer in charge.								
		Sqm							
							0.00	98.17	0.00
	Approved Amount			98.17					
34	Providing and applying painting in two coats with plastic emulsion paint of approved brand on wall surface to give an even approved shade after thoroughly brushing the surface, free from mortar drops and other foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour, complete as per specifications. Extra over Item 15-								
		Sqm							
							0.00	103.63	0.00
	Approved Amount			103.63					
35	Providing skirting, dado, rises of steps with colour glazed tiles on 10mm thick cement plaster 1:3 and jointed with white cement slurry over rough plaster surface (excluding cost of rough plastered surface which should be measured and paid separately) using glazed tiles of approved make and size including cost of materials, labour, complete as per specifications. Colour glazed tiles 30x45 cms 6mm thick with border of size 30 x 10 cms. complete as per specifications and directions of the Engineer in charge.								
		Sqm							

SI No	Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
	Toilet Area Nishargha Park								
			4	3.30		2.10	27.72		
			4	1.65		2.10	13.86		
	Front Portion		1	3.85		2.10	8.09		
	Deduction								
			-2	0.75		1.85	-2.78		
	Toilet								
	Wall Tiles								
	Vivekananda Park								
	Wall								
			4	5.50		2.90	63.80		
			2	5.50		2.90	31.90		
			4	3.00		2.90	34.80		
			8	1.40		2.90	32.48		
	Deduction								
	Door D		-2	0.90		2.10	-3.78		
	Door D1		-8	0.75		2.10	-12.60		
	Ventilator V		-2	3.15		0.50	-3.15		
	Ventilator V1		-2	0.60		0.50	-0.60		
	Window		-2	1.20		1.00	-2.40		
			4	1.50	1.30		7.80		
							195.14		
						Upto 125%	46.08	1390.77	64,079.73
						Above 125%	149.07	1390.77	207315.13
	Approved Amount			1390.77					
36	Providing and fixing Ceramic tiles of size 400x400mm for flooring, threads, steps and landing, laid on a bed of 20mm thick cement mortar 1:3 mix flush pointing with white cement mixed with matching colour pigment including curing, cleaning etc., complete. The work includes cost of all materials, labour charges for all items of work, hire charges for equipment, , etc., complete as per specification. complete as per specifications and directions of the Engineer in charge.								
		Sqm							
	Toilet Area Nishargha Park								
	Floor Area								
			2	1.65	3.00		9.90		
	Vivekananda Park								
	Toilet Floor Area		1	5.50	5.50		30.25		
	deduction								
			-4	1.50	1.30		-7.80		
							32.35		
						Upto 125%	6.75	1148.61	7,753.13
						Above 125%	25.60	1148.61	29,404.48
	Approved Amount			1148.61					

Sl No	Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
37	Providing and laying integral cement based waterproofing treatment including preparation of surface as required for treatment of roofs, balconies, terraces etc., consisting of following application. (a) Applying and grouting a slurry coat of neat cement using 2.75 kg/sqm of cement admixed with proprietary water proofing compound conforming to IS:2645 over the RCC slab after cleaning the surface before treatment. (b) Laying cement concrete using broken brick bats 25mm to 100mm size with 50% of cement mortar 1:5 admixed with proprietary water proofing compound conforming IS:2645 over 20mm thick layer of cement mortar 1:5 admixed with proprietary water proofing compound to required slope and treating similarly the adjoining walls upto 300mm height including rounding off junctions of walls and slabs. (c) After two days of proper curing, applying a second coat of cement slurry admixed with proprietary water proofing compound (d) Finishing the surface with 20mm thick jointless cement mortar of mix 1:4 admixed with proprietary water proofing compound	Sqm							
	Toilet Area Nishargha Park								
			1	4.10	3.85		15.79		
	Vivekananda Park								
	Roof Slab		1	6.40	6.10		39.04		
							54.83		
						Upto 125%	19.76	1097.34	21,686.28
						Above 125%	35.07	1097.34	38,481.14
	Approved Amount					1097.34			
38	SOLID PVC DOOR FRAME Providing & fixing factory made PVC Door frame of size 50x47mm with a wall thickness of 5mm, made out of extruded 5mm rigid PVC foam sheet metered cut at corners & jointed 2 No.s of 150mm long brackets of 15x15mm M.S Square tube, the entire door frame to be reinforced with 19x19mm M.S Square tube of 19 gauge. The door frame to be fixed to the wall using M.S. Screws of 65/80mm size complete as per manufacturers specification & direction of Engineer-in-charge.	Sqm							
	Toilet Area Nishargha Park								
			2	4.45		0.08	0.71		
	Toilet								
	Vivekananda Park								
	Door D1		2	6.00	0.30	0.15	0.54		
							1.25	510.49	639.14
	Approved Amount					510.49			
39	Providing and fixing M.S.grill work for windows and ventilators weighing 21kg/sqm using M.S. flats, or M.S. square rods, or combination of M.S. flats and square rods as per approved design, drawing including cutting steel sections and welding the same to required pattern with a coat of red lead primer, cost of materials, fixtures, labour and HOM of machinery complete as per specifications. complete as per specifications and directions of the Engineer in charge.	Kgs							
	Vivekananda Park								
	Beside Entrance Building		1	2.80	0.90		2.52		
	At Entrance gate		1	2.80	2.00		5.60		
							8.12		

Sl No	Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
	Consider 60kg/sqm Nisargha Park						487.20		
	Ventilators		4	0.75		0.60	1.80		
	At 21kg/Sqm Vivekananda Park		21				37.80		
	Ventilator V		2	3.00		0.50	3.00		
	Ventilator V1		2	0.60		0.50	0.60		
	Window		2	1.20		1.00	2.40		
							6.00		
	Consider 21kg/sqm Deo Marvel Park						126.00		
	Southern Side		1	4.00	0.60		2.40		
	Consider 60kg/sqm Nishargha Park						144.00		
	Stage Entrance								
	Outside Area		1	12.20		3.75	45.75		
	Consider 21kg/sqm						960.75		
	Flat 2inch Pipe		20	0.10		3.75	7.50		
	Consider 10.2kg/sqm						76.50		
	Square 2inch Pipe		4	0.50		3.75	7.50		
	Consider 8kg/sqm						60.00		
	Flat 1.5inch Pipe		20	0.20		3.75	15.00		
	Consider 10kg/sqm						150.00		
	Wheel Bearing		18	2.50		1.20	54.00		
	Consider 6kg/sqm						324.00		
							2366.25		
						Upto 125%	47.25	103.63	4,896.33
						Above 125%	2319.00	103.63	240308.69
	Approved Amount			103.63					
40	Ventilators : Fixed lovers 4'-0" x 3'-0" (1219.2x914.4mm) (Box section) outer frame section size of 33x57mm mullion section. complete as per specifications and directions of the Engineer in charge.								
		Sqm							
	Ventilator		2	0.75	0.90		1.35		
							1.35	3798.17	5,127.52
	Approved Amount			3798.17					
41	SOLID PANEL PVC DOOR SHUTTER Providing & fixing 30mm thick factory made rigid foam Panelled Door Shutters made from M.S. tube of 19 gauge thickness, size 19x19mm fro styles and 15x15mm for top & bottom rails, covered with heat moulded PVC channel of 5mm thick sheet & 30 x 50mm wide to form styles & 5mm thick & 75mm wide PVC Sheets for top rail, lock rail & bottom rail on either side & 5mm thick 20mm wide PVC sheet as gap insert for top rail & bottom rail, Panelling of 5mm thick PVC sheet fitted in the M.S. Frame, Sealed to the styles & rails with 5x30mm PVC sheet beading on either side & joined together with solvent cement adhesive etc., Complete as per manufacturers specification & direction of Engineer-in-charge fixed to frames with 3 nos of 75 m.m Aluminium hinges. complete as per								
		Sqm							
	Toilet Area Nishargha Park								
			2	0.75		2.10	3.15		
	Toilet								

Sl No	Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
	Vivekananda Park						3.15		
	Door D1		4	0.75		2.10	6.30		
							9.45		
						Upto 125%	5.91	3029.15	17,909.86
						Above 125%	3.54	3029.15	10,715.62
	Approved Amount						3029.15		
42	Providing and fixing white vitreous china clay, water closet European type (Pedestal type, P-trap) with black solid plastic seat and lid, C.P brass hinges, rubber buffers, 10 litre low level, P.V.C flushing cistern (all are approved make) with fittings, C.I / M.S brackets, 40mm diameter flush bend with fittings and clamps, overflow arrangements with special and 25mm mosquito proof coupling of approved design, painting of fittings and brackets, cutting and making good the wall and floor wherever required, including cost of materials, labour complete as per specifications. complete as per specifications and directions of the Engineer in charge.								
		No							
			4				4.00		
							4.00		
						Upto 125%	2.50	5406.00	13,515.01
						Above 125%	1.50	5406.00	8,109.01
	Approved Amount						5406.00		
43	Providing and fixing white vitreous china clay, flat back, lipped front urinal basin of 430x260x350mm with 5 litres PVC automatic flushing cistern, C.I / M.S brackets, standard flush pipe and C.P. brass spreaders with brass unions and G.I. clamps complete painting of fittings and brackets, cutting and making good the wall and floor wherever required, including cost of materials, labour complete as per specifications. Specification No. KBS								
		No							
			4				4.00		
						Upto 125%	2.50	3350.94	8,377.34
						Above 125%	1.50	3350.94	5,026.41
	Approved Amount						3350.94		
44	Providing and fixing white vitreous china clay, flat back wash basin size 630x450mm with a pair of 15mm C.P brass pillar taps with C.I / M.S brackets, 32 mm C.P. brass waste of standard pattern, painting of fittings and brackets, cutting and making good the wall and floor wherever required, including cost of materials, labour complete as per specifications. complete as per specifications and directions of the Engineer in charge.								
		No							
			6				6.00		
							6.00		
						Upto 125%	2.50	4370.84	10,927.09
						Above 125%	3.50	4370.84	15,297.92
	Approved Amount						4370.84		
45	Providing and fixing 7.5 cms to 15.00 cms dia NP grating 100 mm dia complete as per specifications and directions of the Engineer in charge.								
		Each							
			8				8.00		
							8.00		
						Upto 125%	5.00	163.62	818.10
						Above 125%	3.00	163.62	490.86
	Approved Amount						163.62		

SI No	Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
46	Providing and fixing to wall, ceiling and floor unplasticised PVC 6.00 kgs/sqcm working pressure with pipe fittings, wall clips etc., and making good the wall, ceiling and floor for sanitary pipelines including cost of all materials, labour charges, HOM of acquirements and testing complete as per specifications. - 160mm dia complete as per specifications and directions of the Engineer in charge.	m	1	60.00			60.00		
							60.00		
						Upto 125%	25.00	930.45	23,261.31
						Above 125%	35.00	930.45	32,565.83
	Approved Amount			930.45					
47	Providing and fixing Chlorinated Poly Vinyl Chloride (CPVC) pipes conforming to IS 15778, having thermal stability for hot and cold water supply including all CPVC plain and brass threaded fittings including fixing the pipe with clamp at 1.00 mtr spacing. This includes jointing of pipes and fittings with one step CPVC solvent cement & the cost of cutting chases & making good the same including testing of joints complete. (Concealed work including cutting chases and good the walls etc.) - 25mm nominal OD pipes	M	1	324.00			324.00		
							324.00		
						Upto 125%	31.25	319.60	9,987.64
						Above 125%	292.75	319.60	93,564.19
	Approved Amount			319.60					
48	Providing and fixing in position brass bib cock of approved quality 25mm nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per specifications. complete as per specifications and directions of the Engineer in charge.	Each	4				4.00		
							4.00	257.43	1,029.72
	Approved Amount			257.43					
49	Constructing brick masonry inspection chamber 600x850mm, and 450mm depth, (clear inside dimension) for pipeline with three or more inlets, using table moulded non-modular bricks of class designation 50 in cement mortar 1:5, C.I cover with frame (light duty) 455x610mm internal dimensions, total weight of cover with frame to be not less than 38 kg (weight of cover 23kg and weight of frame 15 kg) R.C.C. top slab with cement concrete M 15 with 20mm and downsize granite metal , foundation concrete M 5 with 40mm and downsize granite metal inside plastering 12mm thick with cement mortar 1:3, finished smooth with a floating coat of cement on walls and bed concrete complete as per standard design including	Each	8				8.00		
							8.00		
						Upto 125%	2.50	10877.46	27,193.64
						Above 125%	5.50	10877.46	59,826.02
	Approved Amount			10877.46					

No	Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
50	Providing and placing on terrace, polyethylene water storage tanks with manhole lid and suitable locking arrangements, making holes of suitable diameter for inlet, outlet and over flow pipes, including cost of all materials, labour, transport charges, HOM of equipments and testing complete as per specifications (For 1000 litre capacity) complete as per specifications and directions of the Engineer in charge.	Each	3				3.00		
						Upto 125%	2.50	7447.98	18,619.96
						Above 125%	0.50	7447.98	3,723.99
	Approved Amount						7447.98		
51	Providing and laying heavy duty cobble stones 75mm thick interlock pavers, using cement and course sand for manufacture of blocks of approved size, shape and colour with a minimum compressive strength of 281 kg per sqm over 50mm thick sand bed (average thickness) and compacting with plate vibrator having 3 tons compaction force thereby forcing part of sand underneath to come up in between joints, final compaction of paver surface joints into its final level, including cost of materials, labour and HOM of machineries complete as per specifications. (Available Stones) complete as per specifications and	Sqm					0.00	456.48	0.00
	Approved Amount						456.48		
52	Providing and laying heavy duty cobble stones 75mm thick interlock pavers, using cement and course sand for manufacture of blocks of approved size, shape and colour with a minimum compressive strength of 281 kg per sqm over 50mm thick sand bed (average thickness) and compacting with plate vibrator having 3 tons compaction force thereby forcing part of sand underneath to come up in between joints, final compaction of paver surface joints into its final level, including cost of materials, labour and HOM of machineries complete as per specifications. complete as per specifications and directions of the Engineer in charge.	Sqm					0.00	1210.79	0.00
	Approved Amount						1210.79		
53	Providing and laying heavy duty cobble stones 100mm thick interlock pavers, using cement and course sand for manufacture of blocks of approved size, shape and colour with a minimum compressive strength of M40 over 50mm thick sand bed (average thickness) and compacting with plate vibrator having 3 tons compaction force thereby forcing part of sand underneath to come up in between joints, final compaction of paver surface joints into its final level, including cost of materials, labour and HOM of machineries complete as per specifications. complete as per specifications and directions of the Engineer in charge.	Sqm							
	Nisarga Park								
	Stage Left Side								
			1	4.50	3.00		13.50		
	Western Side								
			1	44.30	11.70		518.31		
	Eastern Side								
			1	37.60	10.80		406.08		
	Stage Entrance								
			1	18.00	2.95		53.10		

990.99

Sl No	Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
	Deo marvel Park Gate Entrance						~~990.99~~		
			1	6.20	5.80		35.96		
	Southern Side								
			1	2.20	2.10		4.62		
							1031.57	1191.80	1229425.13
	Approved Amount			1191.80					
54	Supplying and fixing M.S. Rectangular poles made out of 2 equal angles of 65x65x6 mm welded together and fixed in CC (1:2:4) WITH 2 NOS 16mm dia M.S. hold fast rods each of length 25 cms. Including cost of all materials cutting, bending scaffolding wherever necessary, nicely finishing the welded joints with all lead-lifts and as per the directions of the Engineerin - charge of the work and including providing 2 coats of approved quality paint over one coat of shop painting (excluding cost of earthwork and concrete) complete as per specifications and directions of the Engineer in charge.								
		M							
	Vivekananda Park For Fencing B/w Pathway								
			44	2.10			92.40		
	Southern Side								
			20	2.10			42.00		
	Western Side								
			23	2.10			48.30		
							182.70	937.00	171189.39
	Approved Amount			937.00					
55	Providing chain link fencing 50mm size of 8 guage properly stretched between existing rectangular poles and fixed with suitable bolts & nuts, the free ends shall be welded to the pole and block pipe at top and bottom as required including cost of all materials, labour, lead and lifts and as per the directions of the Engineer-in-charge of work including two coats of								
		Sqm							
	Vivekananda Park For Fencing B/w Pathway								
			1	103.40		1.50	155.10		
	Southern Side								
			1	45.80		1.50	68.70		
	Western Side								
			1	59.00		1.50	88.50		
							312.30	779.92	243569.64
	Approved Amount			779.92					
56	Providing and fixing M.S. Block pipe of 38mm dia, of heavy guage of 14 including removing the bends, cutting the pipe, and fixing pipe in between the existing two verticle poles (M.S. rectangular poles) and spot welding the chain link with M.S. block pipe including cost of all materials wastage in cutting, and scaffolding wherever necessary with all lead and lift as directed by the Engineer-in-charge of work etc., complete including two coats of approved quality paint over one coat of shop paint. complete as per specifications and directions of the Engineer in charge.								
		M							

Sl No	Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
	Vivekananda Park								
	For Fencing								
	B/w Pathway		2	103.40			206.80		
	Southern Side		2	45.80			91.60		
	Western Side		2	59.00			118.00		
							416.40	445.05	185317.32
	Approved Amount			445.05					
57	Providing and fixing M.S. Gate as per Chief Architect Drawing, using 50mm x 50mm 14 guage M.S. hollow pipe frame work bent to ornamental shape as shown in the drawing and 35mm x 6mm and 16 x 16mm Square rods for verticals alternatively spaced at 4cms c/c in two halves and 40mmx6mm M.S. flats for horizontal member and at the top cast iron spikes are provided at alternate vertical members as shown in the drawing etc., complete. All the steel								
		Sqm					0.00	3285.49	0.00
	Approved Amount			3285.49					
58	Providing and fixing pre cast solid cement concrete kerb stones made out of CC 1:2:4 with top and bottom width 114 and 165 mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting including formwork, curing, including cost of materials, labour charges of machinery, loading and unloading, lead and lift, transportation etc., complete. complete as per specifications and directions of the Engineer in								
		No							
	Vivekananda Park								
	At Entrance To Cricket Practice Ground								
			2	3.20			6.40		
	Nisarga Park								
	Western Side		1	41.00			41.00		
	Southern Side		1	11.20			11.20		
	Eastern Side		1	31.50			31.50		
	Northern Side		1	41.20			41.20		
	Deo Marvel Park								
	For Kerb Stone								
	Eastern Side		1	82.50			82.50		
	Northern Side		1	92.00			92.00		
	Western Side		1	92.00			92.00		
	Southern Side LHS		1	63.00			63.00		
	Gym Surrounding		1	25.00			25.00		
	Gate Entrance Outside		1	8.50			8.50		

494.30

Sl No	Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
	Shoulder Drain		2	1.10			2.20		
	For Steps		4	0.45			1.80		
	Pole Surrounding		4	0.45			1.80		
	Surrounding		4	0.45			1.80		
	Vivekananda Park								
	Benches Platform		10	3.60			36.00		
	Deo Marvel Park								
	Northern Side		2	16.00			32.00		
	Western Side		2	22.00			44.00		
	Gym Platform		1	23.00			23.00		
							636.90		
							1415.00		
						Upto 125%	547.50	445.05	243662.90
						Above 125%	867.50	445.05	386077.75
	Approved Amount							445.05	
59	Painting two coats after filling the surface with synthetic enamel paint in approved shades on new plastered concrete surfaces, with materials, labour complete as per specifications. complete as per specifications and directions of the Engineer in charge.	Sqm					0.00	87.26	0.00
	Approved Amount							87.26	
60	Providing and applying enamel metal paint one coat (excluding priming coat) on previously painted steel or other metal surface brushing to give an even shade after cleaning oil, grease, dirt and other foreign matter, including cost of materials, labour, complete as per specifications. complete as per specifications and directions of the Engineer in charge.	Sqm					0.00	66.54	0.00
	Approved Amount							66.54	
61	Providing and supplying monoblock single phase motor 1 HP / 0.75 stage as per the directions of engineer in charge complete as per specifications and directions of the Engineer in charge.	Each					1.00		
							1.00	9030.41	9,030.41
	Approved Amount							9030.41	
62	Cost of Haulage including loading and unloading of stone Boulder / Stone aggregates / Sand /Kankar / Moorum KSRRB M100-1: Placing tipper at loading point, loading with front end loader, dumping, turning for return trip, excluding time for haulage and return trip including with all lead and lifts, loading and unloading,tools, plants, HOM of machinery, cost of materials, labour and other incidental charges etc., complete as per specification and as per the direction by Engineer in charge of the work.complete as per specifications and directions of the Engineer in charge.	Cum					0.00		
							0.00	83.43	0.00
	Approved Amount							83.43	

Sl No	Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
63	Open Conduit System Supplying heavy gauge PVC conduit pipe dia mm thick confirming to IS 2509 with suitable size bends, junction boxes, adhesive paste etc., and fixing using inverted wood plugs in case of RCC ceiling and RCC wall / stone structure or rawl plugs in case of brick walls and cement plastering the damaged portion using heavy gauge saddles at an interval of 700mm using NF screws. 19/20mm dia 2mm thick. complete as per specifications and directions of the Engineer in charge.								
		M							
			1	109.00			109.00		
							109.00	50.50	5,504.50
	Approved Amount			50.50					
64	Open Conduit System Supplying heavy gauge PVC conduit pipe dia mm thick confirming to IS 2509 with suitable size bends, junction boxes, adhesive paste etc., and fixing using inverted wood plugs in case of RCC ceiling and RCC wall / stone structure or rawl plugs in case of brick walls and cement plastering the damaged portion using heavy gauge saddles at an interval of 700mm using NF screws. 25mm dia 2mm thick complete as per								
		m							
			1	108.00			108.00		
							108.00	65.65	7,090.20
	Approved Amount			65.65					
65	Concealed Conduit System: Supplying heavy gauge PVC conduit pipe ...mm dia ...mm thick confirming to IS 2509 with suitable size bends, Metal/PVC junction boxes, adhesive paste etc, and running before concreting the slab. The conduit should be tied to the reinforcement rods by using binding wires and unused ways of junction boxes and pipe ends should be covered using PVC end enclosures run with 18SWG GI fish wire where ever necessary. 19/20mm dia								
		m							
			1	19.00			19.00		
							19.00	40.40	767.60
	Approved Amount			40.40					
66	Concealed Conduit System: Supplying heavy gauge PVC conduit pipe ...mm dia ...mm thick confirming to IS 2509 with suitable size bends, Metal/PVC junction boxes, adhesive paste etc, and running before concreting the slab. The conduit should be tied to the reinforcement rods by using binding wires and unused ways of junction boxes and pipe ends should be covered using PVC end enclosures run with 18SWG GI fish wire where ever necessary. 25mm dia 2mm								
		m							
			1	19.00			19.00		
							19.00	53.53	1,017.07
	Approved Amount			53.53					
67	Supplying and flush mounting powder coated / galvanized metal box suitable for mounting modular switch plates. The box should be firmly flush mounted after due groove cutting in Brick/Stone/C.C wall 1-3Way complete as per specifications and directions of the Engineer in charge.								
		Each							
			9				9.00		
							9.00	95.95	863.55
	Approved Amount			95.95					

SI No	Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
68	Supplying and fixing superior quality modular switch mounting polycarbonate plate with necessary supporting back plate with required nos. of machine screws, bolts nuts etc., complete on the existing metal/PVC box. 1-3Way complete as per specifications and directions of the Engineer in charge.	Each	9				9.00	111.10	999.90
	Approved Amount			111.10					
69	Supplying and fixing of modular switch/ Socket/stepped electronic fan regulator/ dimmer/telephone socket etc on existing modular switch plate as per IS 3854 and IS 1293. 6Amps one way. complete as per specifications and directions of the Engineer in charge.	Each	40				40.00	70.70	2,828.00
	Approved Amount			70.70					
70	Supplying and fixing of modular switch/ Socket/stepped electronic fan regulator/ dimmer/telephone socket etc on existing modular switch plate as per IS 3854 and IS 1293. 6Amps 3way socket. complete as per specifications and directions of the Engineer in charge.	Each	25				25.00	95.95	2,398.75
	Approved Amount			95.95					
71	Supplying and fixing of modular switch/ Socket/stepped electronic fan regulator/ dimmer/telephone socket etc on existing modular switch plate as per IS 3854 and IS 1293. Stepped Fan Regulator. complete as per specifications and directions of the Engineer in charge.	Each	20				20.00	292.90	5,858.00
	Approved Amount			292.90					
72	supplying and wiring adopting loop system in existing PVC conduit / casing capping using 1100 v grade , copper conductor flexible multistrand FRLS PVC insulated, 2 x1.5sq.mm cable confirming to the GTP, without switch, the other end of the wires shall be terminated with sufficient loose length in a wood /PVC cound block. complete for each outlet. Short point up to 3Mtr from tapping point to out let via switch box. complete as per specifications	Point	25				25.00	161.60	4,040.00
	Approved Amount			161.60					
73	supplying and wiring adopting loop system in existing PVC conduit / casing capping using 1100 v grade , copper conductor flexible multistrand FRLS PVC insulated, 2 x1.5sq.mm cable confirming to the GTP, without switch, the other end of the wires shall be terminated with sufficient loose length in a wood /PVC cound block. complete for each outlet. Long point above 6Mtr up to 10Mtr from tapping point to out let via switch box. complete as per specifications and directions of the Engineer in charge.	Point	25				25.00		

Sl No	Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
	Approved Amount			378.75			25.00	378.75	9,468.75
74	Supplying and fixing metal Fan box with Round Hook complete as per specifications and directions of the Engineer in charge.	Each							
			20				20.00		
	Approved Amount			85.85			20.00	85.85	1,717.00
75	Wiring for lighting/power circuit using one of FRLS PVC insulated 1100v grade, multistrand Copper with low conductor resistance single core cable in open or concealed system of wiring with specified IS-694:1990 & confirming to GTP of Group-A complete as per specifications and directions of the Engineer in charge.	M							
			1	280.00			280.00		
	Approved Amount			20.71			280.00	20.71	5,797.40
76	Supplying and fixing regular MCB distribution boards on wall/wood board/flush mountin using required clamps, bolts, nuts with provision for fixing suitable type capacity MCB's single phase/3 phase/single door with powder coated painting. Made out of 14 SWG M.S enclosure. Double door 4 way TP & N complete as per specifications and directions of the Engineer	Each							
			8				8.00		
	Approved Amount			784.77			8.00	784.77	6,278.16
77	Supplying and fixing miniature circuit breakers on existing MCB distribution boards using necessary fixing materials and 'C' Type curve, indicator ON/OFF, energy cross-3 with Short circuit breaking capacity of 10K and complete wiring as required confirming to IEC 60898 6-32Amps SP. complete as per specifications and directions of the Engineer in charge.	Each							
			8				8.00		
	Approved Amount			438.34			8.00	438.34	3,506.72
78	Supplying, fixing and wiring eaarth Earth Leakage Miniature Circuit Breaker [ELMCB] 240/250V upto 300mA sensitivity on existing wood/panel board. 16-25Amps 2Pole complete as per specifications and directions of the Engineer in charge.	Each							
			6				6.00		
	Approved Amount			2323.00			6.00	2323.00	13,938.00
79	Supplying and fixing of LED type panel board indicating lamp with required colour suitable for 220v A.C. 50 Hz 12/24v D.C. complete as per specifications and directions of the Engineer in charge.	Each							
			1				1.00		
	Approved Amount			434.30			1.00	434.30	434.30

Sl No	Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
80	Supplying of 2' feet - LED PVC Square Batten ..W with high quality diffuser with Life of 25000 burning hours & 70% lumen maintenance with CRI > 80. Power Input: 220-240V @ 50Hz & Power factor >0.9 along with CE approved drivers. 5 years Warranty against any manufacturing defect working under standard electrical condition LED light fighting 4' - 28 watts. complete as per specifications and directions of the Engineer in charge.	each	18				18.00		
							18.00	252.50	4,545.00
	Approved Amount			252.50					
81	Supplying capacitor type ceiling fan complete with down rod blades, shackle, canopies etc., for operation on 230 volts, 50 cycles. Single phase AC supply conforming to ISS-374-1979 and with double ball bearing system. 56" Sweep (1400mm) Regular moduel. complete as per specifications and directions of the Engineer in charge.	Each	20				20.00		
							20.00	2110.90	42,218.00
	Approved Amount			2110.90					
82	Fixing fluorescent light using 2mtr long 19mm 18 SWG enameled braised conduit of two Nos. rod pendent with ball socket with check nuts all nickel plated complete as per specifications and directions of the Engineer in charge.	Each	30				30.00		
							30.00	496.92	14,907.60
	Approved Amount			496.92					
83	Fixing a ceiling /Wall mounting fan of all capacities and all types to the existing 'S' hook with fan regulator to the existing board together with supplying and fixing 5 amps.ceiling rose,necessary length of 23/0.0076 inch PVC insulated twin twisted copper wire of approved quality, mounted on a suitable aize wooden board and wiredcomplete as per specifications and directions of the Engineer in charge.	Each	20				20.00		
							20.00	262.60	5,252.00
	Approved Amount			262.60					
84	Fixing a ceiling fan with extra length of GI pipe of class B 19mm dia for down rod complete as per specifications and directions of the Engineer in charge.	M	1	40.00			40.00		
							40.00	262.60	10,504.00
	Approved Amount			262.60					

Sl No	Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
85	Supply and fixing of children Multi Play Equipment with curved slide and number panel : Upright structural posts of height 2.4 m, 2.7 m, 3.3 m schedule HOT DIP Galvanized steel with a 114mm OD and 2.2mm (wall) thickness of the tubing. All metal components are to be finished with a baked on powder coat finish. With deck of size 1.45 x 1.45m and Staircase of size 1.5m x 0.77 m are fabricated from 2mm perforated solid punched steel. Deck perimeter is precision pre punched for attachments. Decks are pressed, punched, and welded sand blasted and vinyl plastic coated to a thickness of 4mm. Along with Handrail of height 2.2 m and Dia 32 mm shall be an all-robotic welded unit, fabricated from 32 O.D. galvanized steel pipes with a baked on powder coating finish. Curved Slide of size 1.94 m x 1.85 m x 2.4 m, Panels, Toprails Of Monkey loop of size 1.8 m x 1.3 m. Deck of size 1.45 x 1.45m are fabricated from 2mm perforated solid punched steel. Deck perimeter is precision pre punched for attachments. Decks are pressed, punched, and welded sand blasted and vinyl plastic coated to a thickness of 4mm. Roof of size Dia 2 m and height 0.82 m, Spiral Slide of size 1.16 m x 1.6 m x 3.6 m, Panels The rates are to be inclusive of supply and installation at site. Inclusive of All Taxes and Transportation Charges. complete as per specifications and directions of the	Each					0.00	2223307.95	0.00
	Approved Amount			2223307.95					
86	Supply and fixing of children Multi Play Equipment : Upright structural posts of height 2.35 m , 3.0 m and 3.25 m are to be schedule HOT DIP Galvanized steel with a 114mm OD and 2.2mm (wall) thickness of the tubing. Handrail of height 2.20 m and Dia 32 mm shall be an all-robotic welded unit, fabricated from 32 O.D. galvanized steel pipes with a baked on powder coating finish. Snake Ladder Climber of size 0.99 m x 0.62 m x 1.20 m with thickness of Dia 38 mm, Piped walls of Height 2.6 m are all robotic welded fabricated from 32 O.D. galvanized steel pipes for the outer pipes and 25mm O.D. galvanized steel for the inner parallel bars with a baked on powder coat finish. crab Roof of size 1.9 m x 1.7 m x 0.77m, Sun Roof of size 2.0 m x 1.78 m x 0.77m, Straight slide 2.28 m x 0.83 m x 1.20 m , Spiral Slide of size 2.22 m x 1.60 m x 1.5 m, Rock climber of size 1.03 m x 0.70 m x 1.20 m Panel. The rates are to be inclusive of supply and installation at site. Inclusive of All Taxes and Transportation Charges. complete as per specifications and directions of the Engineer in charge.	Each					0.00	1513889.00	0.00
	Approved Amount			1513889.00					
87	Supply and fixing of children Multi Play Equipment with double swing, curved side toddler slide with animated roof Upright structural posts of height 2.7 m and 3 m are to be schedule HOT DIP Galvanized steel with a 114mm OD and 2.2mm (wall) thickness of the tubing. The poles are welded on to a base plate made from steel with 114mm inner diameter. Deck of size 1.45 x 1.45m and Staircase of size 1.48 m x 0.60 m are fabricated from 2mm perforated solid punched steel. Deck perimeter is precision pre punched for attachments. Handrail of height 1.90 m and Dia 32 mm shall be an all-robotic welded unit, fabricated from 32 O.D. galvanized steel pipes with a baked on powder coating finish. Exposed hardware shall be covered with ultra violet stabilized plastic safety caps as per Sun Roof of size 2.0 m x 1.78 m x 0.77m, Spiral Slide of size 2220 mm x 1630 mm x 1880 mm , Straight Slide of size 1645 mm x 800 mm x 1140 mm, Panels. Roofs and panels are copyrighted and IP protected worldwide. Spring Climber of thickness Dia 38 mm, 3 step ladder , Frisbee Climber , Piped walls of Height	Each					0.00	1228887.20	0.00
	Approved Amount			1228887.20					

Sl No	Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
88	Supply and fixing of children Play Equipment Fiero A Swing : Shaped structural posts of height 2.31 m are to be schedule HOT DIP Galvanized steel with a 114mm OD and 2.2mm (wall) thickness of the tubing. Plastic Components such as swing seats [super thick plastic] shall be animated and shall be rotationally molded from antistatic, copolymer, virgin linear low density UV stabilized polyethylene, with color molded in and minimum thickness of 6 - 8mm. The rates are to be inclusive of supply and installation at site. Inclusive of All Taxes and Transportation Charges, complete as per specifications and	Each					0.00	128160.92	0.00
	Approved Amount			128160.92					
89	Supply and fixing of children Play Equipment Two seater seesaw : The See Saw consists of 2 poles of Dia 114mm and thickness of 2.5mm which balances the horizontal rod at the center which is of size 3110 mm length and Dia 114 mm. It consists of 2 seats which is made of LLDPE virgin plastic of size 305mm X 213 mm X 125 mm. The rates are to be inclusive of supply and installation at site. Inclusive of All Taxes and Transportation Charges, complete as per specifications and directions of the Engineer in charge.	Each					1.00	84312.78	84,312.78
	Approved Amount			84312.78					
90	Supply and fixing of children Play Equipment Merry go round - DX : The Merry go round consists of a round platform which is made of galvanized steel and has a thickness of 2.5 mm. It is also power coated with the thickness of 2.5 mm. It is of Dia 1210 mm. It has 3 inverted "L" shaped handrails which is made of Galvanized steel and of dimensions as 474 mmx 815 mm. It has thickness of Dia 32 mm. The 3 handrails are separated exactly. All the 3 handrails are connected to the Centre with the help of a rod which is also made of Galvanized steel and of Dia 48 mm and height 815 mm. The rates are to be inclusive of supply and installation at site. Inclusive of All Taxes and Transportation Charges, complete as per specifications and directions of the Engineer in charge.	Each					0.00	85890.40	0.00
	Approved Amount			85890.40					
91	Supply and fixing of children Play Equipment Puppy dog Rider / Elephant rider / Horse rider : : HDPE of size 0.83 m x 0.31 m x 0.87 m, Plastic Components [super thick plastic] shall be rotationally molded from antistatic, copolymer, virgin linear low density UV stabilized polyethylene, with "color molded" in not "added in". All rotational molding is carried out in state of the art, precision, bi axial roto moulding machines which helps achieve guaranteed uniform wall thickness, seamless joints, accurate process control, one part construction to make it stress free. Specialized connectors such as clamps and couplings are to be cast from aluminium which is pre-treated, and cured, with a baked on powder coat finish. The rates are	Each					0.00	56333.76	0.00
	Approved Amount			56333.76					
92	Dismantling barbed wire or flexible wirer rope in fencing including making rolls and stacking within 50m lead. including cost of materials, labour, HOM complete as per specifications. complete as per specifications and directions of the Engineer in charge.	Mtr							

Sl No	Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
	Compound Wall								
	Hanuman Temple Yelahanka								
	North Side LHS Gate		1	13.00		1.50	19.50		
	North Side RHS Gate		1	15.00		1.50	22.50		
	Eastern Side		1	22.40		1.60	35.84		
	Southern Side		1	23.00		1.30	29.90		
	Western Side		1	6.00		1.20	7.20		
	Park Inside Temple								
	Northern Side		1	5.00		1.20	6.00		
	Southern Side		1	6.00		1.00	6.00		
	Eastern Side		1	20.00		1.00	20.00		
	Western Side		1	19.00		1.00	19.00		
	Shankar Nag Park								
	Western Side		1	70.00		1.50	105.00		
	Southern Side		1	50.00		1.40	70.00		
	Northern Side		1	46.00		1.60	73.60		
	Eastern Side		1	58.00		1.20	69.60		
							484.14	7.49	3,628.24
	Approved Amount			7.49					
93	Earthwork excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in hard soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. after breaking of clods complete as per specifications. complete as per specifications and directions of the Engineer in charge.								
		Cum							
	Hanuman Temple Yelahanka								
	North Side LHS Gate		1	13.90	1.20	1.25	20.85		
	North Side RHS Gate		1	19.70	1.20	1.25	29.55		
	Eastern Side		1	86.40	1.20	1.25	129.60		
	Southern Side		1	24.40	1.20	1.25	36.60		
			1	14.00	1.20	1.25	21.00		
	Western Side		1	86.30	1.20	1.25	129.45		
	Park Inside Temple for fencing								
	Northern Side		4	0.30	0.30	0.50	0.18		
	Southern Side		4	0.30	0.30	0.50	0.18		
	Eastern Side		10	0.30	0.30	0.50	0.45		
	Western Side		10	0.30	0.30	0.50	0.45		
	Hanuman Temple Yelahanka								
	For Benches		1	2.00	1.40	0.30	0.84		
	RHS of Temple		1	1.90	1.30	1.30	3.21		
			1	3.80	1.40	0.30	1.60		
	Infront of Statue		1	3.40	1.40	0.30	1.43		
	LHS of Temple		1	7.50	1.10	0.30	2.48		
	Shankar Nag Park								
	Western Side		1	80.00	1.20	1.10	105.60		
	Southern Side		1	104.00	1.20	1.10	137.28		
	Northern Side		1	74.00	1.20	1.10	97.68		
	Eastern Side		1	84.00	1.20	1.10	110.88		

829.30